

TABLE A: BILL OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
A	<u>Bill No 1</u>				
	<u>ALTERATIONS</u>				
	<p>Tenderers are advised to study the Model Preambles for Trades before pricing this Bill</p> <p>The contractor is specifically requested to visit the site and ascertain for him/herself the items to be removed described hereunder</p>				
	<u>FLOORS</u>				
	<u>Remove existing Ceramic floor tiles, Skirting and prepare floors</u>				
1.00	On floors	m ²	120		
2.00	Making good by means of self-levelling screed to receive new ceramic tiles	m ²	120		
	Total amount Carried to Final Summary				R

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
B	Bill No 2				
	TILLING				
	Tenderers are advised to study the Model Preambles for Trades before pricing this Bill SUPPLEMENTARY PREAMBLES <u>Fixing</u> Ceramic, porcelain, marble and granite tiles are to be fixed and grouted with suitable adhesives and grouts from the "Tal Professional" range of products as recommended by the manufacturer of the tiles				
	FLOOR TILING				
	<u>Supply and Install Urbane Grey Matt Ceramic Floor Tile -430 x 430mm or similar approved, fixed to internal floor screed with tal gold star 6 rapid setting tile adhesive mixed with tal bond bonding liquid in lieu of water on prepared floors, using a tal notched trowel, and 3mm joints continuous in both directions, jointed and flush pointed with tal professional Light Grey Grouting</u>				
1.00	On floors	m ²	120		
2.00	Skirting	m	22		
3.00	Supply 2 x boxes of 430 x 430mm urbane tiles for spare	no	2		
	CORNER PROTECTORS, DIVIDING STRIPS, ETC				
	"Kirk Marketing"				
3.00	Stainless steel straight edge trims (to match existing)	m	22		
	Total amount Carried to Final Summary				R

FINAL SUMMARY

ITEM	DESCRIPTION	PAGE	AMOUNT
A	BILL NO 1: ALTERATIONS	3	R
B	BILL NO 2: TILLING	4	R
	NOTE: Contractor is requested to carefully work and clean all areas that has been shown to him / her. Contractor is also requested to clean or paint all areas affected by his or her work to match existing paint work of the structure.		
	SUB-TOTAL		R
	V.A.T @ 15%		R
	TOTAL		R